



Chandler • Arizona
Where Values Make The Difference

C.

MAR 07 2012
Chandler



MEMORANDUM

Transportation & Development – PZ Memo No. 12-017

DATE: FEBRUARY 23, 2012

TO: PLANNING AND ZONING COMMISSION

THRU: R.J. ZEDER, TRANSPORTATION & DEVELOPMENT DIRECTOR
JEFF KURTZ, PLANNING ADMINISTRATOR *[Signature]*

FROM: KEVIN MAYO, PLANNING MANAGER *KM*

SUBJECT: PDP11-0015 TEMPE KOREAN PRESBYTERIAN CHURCH

Request: Preliminary Development Plan (PDP) approval for the construction of a shade Ramada in conjunction with outdoor fellowship and playground space

Location: Northwest corner of Dobson Road and the Loop 202 Santan Freeway

Applicant: Susan Billings
Elevated Design Studio, LLC.

Project Info: 11.5-acre church campus, 2,000 square-foot Fellowship Ramada, 3,000 square-foot Playground Ramada

RECOMMENDATION

Upon finding the request to be consistent with the General Plan and in conformance with the site's Planned Area Development (PAD) zoning, Staff recommends approval subject to conditions.

BACKGROUND

The approximate 11.5-acre subject site received initial zoning for a church facility in July 2002, and was extended for an additional 3 years in 2004. The original approval, formerly known as Wellspring Church, included an elaborate campus master plan consisting of a 27,000 square-foot/1,200 seat worship center, a 26,000 square-foot multi-use building (Building A) that contained additional classrooms and an auditorium/sports court, and a 30,000 square-foot multi-use building (Building B) containing classrooms and meeting rooms. Additional site features

included a wedding grove, a prayer garden, playgrounds, fountains, pedestrian connections and recreational fields at the western end of the property. A subsequent PDP approval enabled the construction of a scaled-down 15,400 square-foot multi-use building (Building A) as Phase I with associated site improvements. The remaining buildings and site improvements as part of the campus master plan have not been constructed.

The Tempe Korean Presbyterian Church (TKPC) recently purchased the church property. The congregation has identified the need for outdoor fellowship space as well as an outdoor playground. The subject request is PDP approval for the construction of a 2,000 square-foot Fellowship Ramada, adjacent to a 3,000 square-foot Playground Ramada, to be located in the area originally identified in the campus master plan as the 'Wedding Grove'. This area will remain important connective space for the future 30,000 square-foot Building B, and the balance of the campus.

The two shade ramadas are essentially one 45-foot wide by 96-foot long structure featuring independent canopy heights and shading material. The structure will be constructed using metal columns and beams. The beams will include chamfered ends similar to the existing building's exposed tapered decorative beams. All frame work will be painted dark brown to match the building's trim color. Canopy heights have been set in accordance to the activities beneath them. The larger Playground Ramada is set at 16-feet in height to accommodate the playground equipment. The smaller Fellowship Ramada portion is set at 10'-9" in height. The shading material over the Playground Ramada will be flat, laced shade fabric. Metal hat channel will be used for shading over the Fellowship Ramada adding material diversity and complimenting the existing architecture.

Landscaping improvements will include a row of 24"-box Desert Museum Palo Verde trees lining the east and west sides of the ramadas. Three additional Shoestring Acacia trees will be added along the southern property line adjacent to the freeway. Finally, the existing storage container and 6-foot block wall will be relocated further west and include a full-height block wall painted to match the building. This temporary storage container will be removed once the future classroom building is constructed.

DISCUSSION

Staff supports the proposed PDP finding the simplistic design to complement the existing architecture. Shaded outdoor gathering space has always been contemplated within the campus master plan, and the proposed location will remain central to the overall campus.

PUBLIC / NEIGHBORHOOD NOTIFICATION

- This request was noticed according to the provisions of the City of Chandler Zoning Code.
- A Neighborhood meeting was held on January 30, 2012 at the Tempe Korean Presbyterian Church. No neighboring property owners attended the meeting.

At the time of this writing, Staff has received no phone calls or letters in opposition to this request.

RECOMMENDED ACTION

Upon finding consistency with the General Plan, Staff recommends approval of the Preliminary Development Plan (PDP), subject to the following conditions:


1. Development shall be in substantial conformance with Exhibit A, Development Booklet, entitled "Tempe Korean Presbyterian Church", kept on file in the City of Chandler Planning Services Division, in File No. PDP11-0015, except as modified by condition herein.
2. Compliance with the original stipulations adopted by the City Council as Ordinance 3384, case DVR02-0011 WELLSPRING CHURCH ON DOBSON, except as modified by condition herein.
3. The site shall be maintained in a clean and orderly manner.
4. The landscaping shall be maintained at a level consistent with or better than at the time of planting.
5. The canvas shade structures shall be maintained in a manner similar to that at the time of installation.

PROPOSED MOTION


Motion to recommend approval of the Preliminary Development Plan in case PDP11-0015 TEMPE KOREAN PRESBYTERIAN CHURCH, subject to the conditions recommended by Staff.

Attachments

1. Vicinity Maps
2. Site Plan
3. Landscape Plan
4. Elevations
5. Exhibit A, Development Booklet




Vicinity Map



PDP11-0015

Tempe Korean Presbyterian Church



Vicinity Map




PDP11-0015

Tempe Korean Presbyterian Church



Chandler • Arizona
Where Values Make The Difference


CITY OF CHANDLER 11/15/2011



DOBSON ROAD

CONCRETE REACTIVE

1 OVERALL SITE PLAN
DATE: 11-2012



2 DETAILED SITE PLAN
DATE: 11-2012

GENERAL NOTES

- A. ALL DIMENSIONS ARE TO STRUCTURAL GRID, FACE OF CHILL, FACE OF CONCRETE, OR FACE OF STUD. UNLESS OTHERWISE NOTED AS "CLEAR" ARE FROM FACE OF FINISH.
- B. EXCEPT WHERE NOTED AS EXPANSION JOINT, ALL OTHER CONCRETE SCORE LINES TO BE CONTROL JOINTS. SEE DETAILS.

KEY NOTES

1. PROPERTY LINE.
2. 10' SETBACK LINE.
3. EXISTING PARKING TO REMAIN.
4. EXISTING RETENTION BASINS TO REMAIN.
5. NEW LANDSCAPE AREA - SEE LANDSCAPE PLAN.
6. PHASE 2 LIMIT LINE.
7. EXISTING TO REMAIN.
8. EXISTING TRANSFORMER TO REMAIN.
9. PROVIDE NEW CONCRETE HARDSCAPE WITH CONTROL JOINTS AS SHOWN. CONCRETE COLOR AND FINISH TO MATCH EXISTING ADJACENT CONCRETE.
10. LINE OF NEW PLAYGROUND RAMADA ABOVE.
11. PLAYGROUND EQUIPMENT BY OWNER. PROVIDE 12" MIN. COMPACTED DEPTH/10% FILL FALL SURFACING (ENGINEERED FIBER). IN EXISTING PLAYGROUND OPTION: POURED RUBBER PLAY SURFACE AT OWNER SELECT AREA. SEE DETAILS 8 & 9 ON A&L.
12. NEW 48" H PAINTED (JUNN EDWARDS DESIGN) BLACK WALNUT 1" METAL VIEW FENCE AT PERIMETER OF PLAYGROUND. PROVIDE 15.38" W GATE WITH SELF-CLOSING HINGE AND LATCH. SEE DETAIL TAKE 2.
13. LINE OF NEW FELLOWSHIP RAMADA ABOVE.
14. RELOCATED STORAGE CONTAINER TO BE COMPLETELY SCREENED FROM VIEW WITH STUCCO FINISHED MASONRY WALL WITH PAINTED METAL ACCESS GATE. STORAGE CONTAINER TO BE TEMPORARY STORAGE FOR CHURCH UNTIL PHASE 3 CLASSROOM BUILDING IS CONSTRUCTED. SEE DETAILS ON A&L AND STRUCTURAL DRAWINGS.
15. EXISTING SCREEN HALL AROUND EXISTING STORAGE CONTAINER TO BE DEMOLISHED. STORAGE CONTAINER TO BE RELOCATED.
16. PROVIDE POWER TO SECURITY LIGHTS. SEE ELECTRICAL DWGS.



4035 ROAD COCAWING STREET
SPRING, AZ 85344
480.232.8490

PRELIMINARY
NOT FOR
CONSTRUCTION

DOCUMENT CONTROLLED IN 2012
THIS DOCUMENT IS THE PROPERTY OF ELEVATED DESIGN STUDIO AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF ELEVATED DESIGN STUDIO.

AN ELEVATED DESIGN FOR:
TKPC
1150 S. Dobson Rd.
Chandler, AZ 85286


TEMPE KOREAN PRESBYTERIAN CHURCH
FELLOWSHIP AND PLAYGROUND RAMADA
1150 South Dobson Road
Chandler, AZ 85286

Revision Log

Issue Date 02.15.12


EDS Project # #11-012

A1.0



KEY MAP

SCALE: NTS
 Ref. North



CONCEPTUAL PLANTING PLAN

SCALE: 1"=20'-0"
 Ref. North

MASTER PLANT LIST	
TREES	SIZE/COMMENTS
+	EXISTING TREE (TO BE REMOVED OR RELOCATED) 10 QTY
●	CERCIDILUM HYBRID PALO VERDE DESERT MUSEUM PALO VERDE OPTION: DALBERGIA OR ACACIA 24" BOX, 7' HEIGHT LOW-BREAKER MATCHED, QTY 12
+	ACACIA STENOPHYLLA SHOESTRING ACACIA 24" BOX, 12' HIGH MIN. LOW-BREAKER MATCHED, QTY 3
SHRUBS	
○	LEUCOPHYLLUM LAEVIGATUM 'RIO BRAVO' 5 GAL. QTY 25
⊖	RUELLIA PENINSULARIS DESERT RUELLIA 5 GAL. QTY 24
GROUNDCOVER	
A	LANTANA SPECIES 'NEW GOLD' NEW GOLD LANTANA 1 GAL./O.C., QTY 16
DG	DECOMPOSED GRANITE SIZE AND COLOR TO MATCH EXISTING 2" THICK TYP.

GENERAL NOTES

- ALL DECOMPOSED GRANITE TO MATCH SIZE AND COLOR OF EXISTING 2" THICK TYP. ALL PLANTING AREAS
- CONTRACTOR TO VERIFY ALL CONDITIONS IN FIELD, PRIOR TO CONSTRUCTION. NOTIFY LANDSCAPE ARCH. IF CONFLICT ARISES.
- VERIFY ALL CONDITIONS IN FIELD PRIOR TO BIDDING/CONSTRUCTION. CONTRACTOR TO NOTIFY CONSULTANT OF ANY DISCREPANCY, IN WRITING, WITHIN 72 HOURS OF DISCOVERY, OR ASSUME FULL LIABILITY.

CITY OF CHANDLER NOTES

ALL PLANT MATERIAL ARE GUARANTEED FOR A MINIMUM PERIOD OF 60 DAYS FROM THE DATE OF FINAL APPROVAL BY THE CITY. ANY PLANT MATERIAL WHICH ARE NOT APPROVED BY THE CITY PRIOR TO OCTOBER 1ST OF THE CALENDAR YEAR IN WHICH THEY ARE INSTALLED, SHALL BE FURTHER GUARANTEED UNTIL MAY 25TH OF THE FOLLOWING CALENDAR YEAR.

TREES, SHRUBS, VINES, GROUNDCOVER, AND TURF WHICH HAVE BEEN REPLACED UNDER TERMS OF THE GUARANTEE, SHALL BE GUARANTEED FOR AN ADDITIONAL 60 DAYS FROM THE DAY OF REPLACEMENT.

ALL PLANT MATERIALS MUST BE MAINTAINED IN HEALTH AND VIGOR AND BE ALLOWED TO ATTAIN NATURAL SIZE AND SHAPE IN ACCORDANCE WITH THE ORIGINALLY APPROVED LANDSCAPE PLAN.

ALL SITE IMPROVEMENTS, INCLUDING LANDSCAPE AND SITE CLEANUP MUST BE COMPLETED PRIOR TO A CERTIFICATE OF OCCUPANCY BEING ISSUED FOR ANY BUILDING WITHIN A PHASE.

ALL TREES SHALL COMPLY WITH THE LATEST AMENDED EDITION OF THE "ARIZONA NURSERY ASSOCIATION RECOMMENDED TREE SPECIFICATIONS"

PARKING LOT TREES MUST HAVE A MINIMUM CLEAR CANOPY DISTANCE OF 5'.

FINISH GRADE OF LANDSCAPE AREAS (TURF/DG) MUST BE GRADED TO 1-1/2" BELOW CONCRETE OR OTHER PAVED SURFACES.

TREES MUST BE PLANTED A MINIMUM OF 5' FROM SIDEWALKS, PUBLIC ACCESSWAYS, SHRUBS MUST BE, AT MATURITY, 3' FROM ALL SIDES OF FIRE HYDRANTS.

THERE SHALL BE NO OBSTRUCTION OF SITE SIGNAGE BY LANDSCAPE PLANT MATERIAL, AND THAT SUCH MUST BE RELOCATED/CORRECTED BEFORE THE FIELD INSPECTION WILL ACCEPT/PASS THE SIGN IN THE FIELD OR ISSUE A CERTIFICATE OF OCCUPANCY FOR A PROJECT.

ALL LANDSCAPING SHALL BE MAINTAINED BY THE LANDOWNER OR THE LESSOR, SECTION 1902 (8) (a), ZONING CODE.

ALL TRANSFORMER BOXES, METER PANELS, AND ELECTRIC EQUIPMENT, BACKFLOW DEVICES AND ANY OTHER UTILITY EQUIPMENT, NOT ABLE TO BE SCREENED BY LANDSCAPING OR WALLS SHALL BE PAINTED TO MATCH THE BUILDING COLOR, SECTION 1902 (8) (a) (14), ZONING CODE.

SIGNS REQUIRE SEPARATE PERMIT.

ALL LANDSCAPING SHALL BE MAINTAINED BY THE LANDOWNER OR THE LESSOR.

ALL EXTERNAL LIGHTING SHALL BE LOCATED AND DESIGNED TO PREVENT RAYS FROM BEING DIRECTED OFF OF THE PROPERTY UPON WHICH THE LIGHTING IS LOCATED.

I HEREBY CERTIFY THAT NO TREE OR BOULDER IS DESIGNED CLOSER THAN 8' TO THE FACE OF THE STREET CURB.

[Signature]

REGISTERED LANDSCAPE ARCHITECT DATE



2008/08 COPYRIGHT © 2011
 4000 90TH COCONINO STREET
 PHOENIX, AZ 85044
 480.251.8490

TKPC
 1150 S. Dobson Rd.
 Chandler, AZ 85286

TEMPE KOREAN PRESBYTERIAN CHURCH
 FELLOWSHIP AND PLAYGROUND RAMADA
 1150 South Dobson Road
 Chandler, AZ 85286


Revision Log

Issue Date 11.04.11


EOS Project # #11-012



L1.0



1 FLOOR PLAN
SCALE: 1/4" = 1'-0"



2 CANOPY PLAN
SCALE: 1/4" = 1'-0"

GENERAL NOTES

- A. ALL DIMENSIONS ARE TO STRUCTURAL GRID, FACE OF WALL, FACE OF CONCRETE, OR FACE OF STUD. L.I.V.D. DIMENSIONS NOTED AS "CLEAR" ARE FROM FACE OF FINISH.
- B. EXCEPT WHERE NOTED AS EXPANSION JOINT, ALL OTHER CONCRETE SHALL BE CONTROL JOINTS. SEE DETAILS.



4030 East Coccurring Street
Phoenix, AZ 85044
480.222.8475

KEY NOTES


- 1. PAINTED (DUNN EDWARDS DENIRO 'BLACK WALNUT') METAL TUBE STEEL COLUMN.
- 2. PAINTED (DUNN EDWARDS DENIRO 'BLACK WALNUT') METAL BEAM OR PURLIN ABOVE.
- 3. NEW CONCRETE SLAB WITH CONTROL JOINTS AS SHOWN. CONCRETE COLOR AND FINISH TO MATCH ADJACENT EXISTING CONCRETE.
- 4. NEW 4" H PAINTED (DUNN EDWARDS DENIRO 'BLACK WALNUT') 1 1/2" METAL VIEW FENCE AT PERIMETER OF PLAYGROUND. PROVIDE (1) 3" W/SHOTS WITH SELF-CLOSING HINGE AND LATCH. SEE DETAIL T3A.2.
- 5. 20 YEAR OLD AND 5-10 YEAR OLD PLAYGROUND EQUIPMENT BY OWNER. PROVIDE 12" O.H.S. COMPACTED DEPTH/GRADE FULL PALL SURFACING (ENGINEERED WOOD FIBER) IN ENTIRE PLAYGROUND. OPTION: POURED RUBBER PLAY SURFACE AT OWNER SELECT AREA. SEE DETAILS 8 & 9 ON A4.2.
- 6. MECHANICALLY FASTENED (LACED) COMMERCIAL GRADE SHADE CLOTH (SOLAR 'BLUET') FABRIC TO MEET ASTM 84. CLASS III FIRE RETARDANT.
- 7. FELLOWSHIP RAMADA ONLY: PAINTED (DUNN EDWARDS DENIRO 'BLACK WALNUT') 1-1/2" METAL HAT CHANNEL SPACED 1'-0" APART AS SHOWN ELEMENT MECHANICALLY FASTENED TO STRUCTURE. SEE STRUCTURAL DRAWINGS.

PRELIMINARY
NOT FOR CONSTRUCTION

DOCUMENT COPYRIGHTED BY 2012
OFFICE OF ELEVATED DESIGN STUDIO
1150 South Dobson Road
Chandler, AZ 85286

AN ELEVATED DESIGN FOR:
TGPC
1150 S. Dobson Rd.
Chandler, AZ 85286

BUILDING MATERIALS EXHIBIT




TEMPE KOREAN PRESBYTERIAN CHURCH
 FELLOWSHIP AND PLAYGROUND RAMADA
 1150 South Dobson Road
 Chandler, AZ 85286

Revision Log

Issue Date: 02.15.12
EDS Project #: #11-012

A2.0




1 SOUTH ELEVATION
SCALE: 1/8" = 1'-0"




3 WEST ELEVATION
SCALE: 1/8" = 1'-0"




5 NORTH ELEVATION
SCALE: 1/8" = 1'-0"



2 SOUTH ELEVATION - CONTAINER ENCLOSURE
SCALE: 1/8" = 1'-0"



4 WEST ELEVATION - CONTAINER ENCLOSURE
SCALE: 1/8" = 1'-0"



GENERAL NOTES

- ALL DIMENSIONS ARE TO STRUCTURAL GRID, FACE OF CONCRETE, OR FACE OF STUD. UNLESS DIMENSIONS NOTED AS "CLEAR" ARE FROM FACE OF FINISH.
- EXCEPT WHERE NOTED AS EXPANSION JOINT, ALL OTHER CONCRETE SCORE LINES TO BE CONTROL JOINTS. SEE DETAILS.

KEY NOTES

- LINE OF FUTURE BUILDING
- PAINTED (ICI "ARTISAN BROWN") METAL T.S. COLUMN / BEAM / PURLIN.
- PAINTED (ICI "ARTISAN BROWN") METAL BEAM EXTENSION (1'-0") WITH WELDED CONNECTION AND TAPERED BEAM ENDS (TYPICAL).
- SHADE ELEMENT AT FELLOWSHIP RAMADA. PAINTED (ICI "ARTISAN BROWN") METAL HAT CHANNEL SPACED 2" APART AS SHADE ELEMENT, MECHANICALLY FASTENED TO STRUCTURE.
- NEW 4" x 4" POWDER COATED (TO MATCH (ICI "ARTISAN BROWN") 1 1/2" METAL VIEW FENCE AT PERIMETER OF PLAYGROUND. PROVIDE 1/2" x 3/4" WHITE SELF-CLOSING HINGE AND LATCH LOCK.
- SHADE ELEMENT AT PLAYGROUND RAMADA. MECHANICALLY FASTENED FACED COMMERCIAL GRADE SHADE CLOTH (COLOR: SEDONA RED, RUSTY OR NAVY). FABRIC TO MEET ASTM A1 CLASS IN FIRE RETARDANT.)

BUILDING MATERIALS EXHIBIT

- DULUX EDWARDS DESO "BLACK WALNUT", SEMI-GLOSS
- COLOR: "RUSTY" BY TENSION SHADE CLOTH, ASTM A1 CLASS IN FIRE RETARDANT



4330 WEST CUCUMBER STREET
PHOENIX, AZ 85044
480.323.5495

PRELIMINARY
NOT FOR
CONSTRUCTION

©2011 ELEVATED DESIGN STUDIO
ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM ELEVATED DESIGN STUDIO.

AN ELEVATED DESIGN FOR:
TKPC
1150 S. Dobson Rd.
Chandler, AZ 85286

TEMPE KOREAN PRESBYTERIAN CHURCH
FELLOWSHIP AND PLAYGROUND RAMADA
1150 South Dobson Road
Chandler, AZ 85286

Revision Log

Issue Date 02.15.12
EDS Project # #11-012

A3.0
TAKING OFF PUBLIC COPY